




CM PUMPS AND SYSTEMS PVT. LTD.

Manufacturer of Magnetic Drive Sealless Pumps & Agitators

"For clean & green environment"

Metallic Magnetic Drive Sealless Chemical Process Pump



TÜV
AUSTRIA

CERTIFIED

TÜV AUSTRIA CERT GMBH

EN ISO 9001

20100163001473

EN ISO 14001

20104173002775

ISO 45001

20116203009283



ATEX 2014/34/EU



About Us

We are the Pioneer and the first Indian Manufacturer and Exporter of Sealless Magnetic Drive Centrifugal pumps used for the Industrial Segments – Chemical Process Industries, Pharmaceutical industries, Petrochemical Industries, Refineries, Water treatment plant, Metal processing industries, Recycling industries, Refrigeration industries, Heating plant and Tank storage. We offer a wide range in Magnetic Drive Centrifugal Pumps according to DIN EN 22858/ISO 2858 Standards.

Our Sales and Service support team is always prompt to serve you better and provide professional and seamless service. CM Pumps and Systems Pvt Ltd has engaged the services of leading Management Consultant to train and develop all CM Pumps personnel to serve their customers professionally and efficiently



Our Mission and Moto

The mission and moto is to successfully develop and produce superior quality and energy efficient pump sets at right price for global market.

Our Vision

Our Vision is to be the environment friendly, global manufacturer and supplier of high efficiency and excellent quality multi application Magnetic Drive centrifugal pumps sets.

Our Team

The reason behind our enviable leadership in global market is the result of sustained work comes from our competent professionals. They are not only highly qualified but also are consistently working towards improvising on our innovative range of pumps as per prevailing quality standards. Our professionals make full use of available facilities to cater to ever increasing demands of various Industries.

Our team comprise:


- Engineers
- Technicians
- Quality Controllers
- Research Associates

Our professionals keep themselves abreast and equivalent with latest technology and work in sync to cater to specific and customized demands of our clients. Their unstinted support and service have enabled us to come up with innovative products for our esteemed client.



Why us?

- Professional and well Managed Pvt. Ltd. Co.
- State-of-the-art infrastructure.
- Superior quality with right price.
- Shortest delivery period, with proven quality products.
- Readiness to offer required technical support.
- Prompt after sales services.
- Client-centric approach.
- Experienced professionals-competent & committed.
- Modern management technique.
- Effective quality controls measures
- Research oriented professionals.

Certifications




CZ Close Coupled Pump Series - **Metalic Magnetic Drive Sealless Chemical Process Pump**



Description

- Single Stage, Horizontal Centrifugal Pump.
- Hydraulic Performance and Dimensions according to DIN EN ISO 2858
- Technical design based on DIN EN ISO 15783
- Permanent Magnetic Drive for wide range of temperature.
- Maintenance Free
- Separation of Liquid Chamber to Atmosphere by Means of Isolation Shell
- Slipless Power Transfer
- Materials : Steel, Stainless Steel, Nickel Based Materials
- Close Coupled Block Design
- Hydraulically balanced impeller for minimum bearing loads
- Product-Lubricated Journal Bearings; made of Sintered Silicon Carbide (SSiC) or Customized Materials

CZ Close Coupled Pump Series - Metalic Magnetic Drive Sealless Chemical Process Pump



Technical Data

Operation Range
 Flow Rate : max. 300m³/h
 Delivery Head : max. 100 metre
 Pressure Rating : Class 150
 Temperatures : -35°C to +250°C
 Kinematic viscosities : 0.5 to 500 mm²/s

Casing & Impeller Materials

Stainless steel SS 316, SS 316L, SS 304, SS 304L
 Other materials duplex alloys , nickel-base alloys
 (e.g. Hastelloy®),

Working Principle	:	Radial flow pump
Stages	:	Single stage
Priming Method	:	Flooded suction
Sealing System	:	Magnetic coupling
Standards	:	DIN EN ISO 2858
Standards	:	DIN EN ISO 15783
ATEX	:	2014/34/EU
	:	Ⓔ II 2 GD c T2

2 POLE (2900 RPM)



Pump Model	Size Description			Nominal duty point		Dimension in millimetres															
	Ø inlet mm	Ø outlet mm	impeller (nominal) mm	Q m³/h	H m	Pump				Support								Motor			
						a	f	h1	h2	h3	m1	m2	m3	n1	n2	S1		hp	kw	rpm	Rated amps
CZ 25 x 25 -125	25	25	125	4	20	82	425	112	142	340	465	405	62	300	270	Ø16		1	0.75	2900	1.6
CZ 32 x 25 -125	32	25	125	5	20	82	475	112	142	340	465	405	62	300	270	Ø16		1.5	1.1	2900	2.3
CZ 32 x 25 -150	32	25	150	5	30	82	475	112	142	340	465	405	62	300	270	Ø16		2	1.5	2900	3.1
CZ 50 x 32 -125	50	32	125	12.5	20	80	665	112	140	338	604	554	46	338	308	Ø16		3/5	2.2/3.7	2900	4.3/7
CZ 50 x 32 -160	50	32	160	12.5	32	80	665	132	160	380	604	554	46	338	308	Ø16		5/7.5	3.7/5.5	2900	7/10
CZ 50 x 32 -200	50	32	200	12.5	50	80	720	160	180	430	700	675	50	350	320	Ø16		10/12.5	7.5/9.3	2900	13.7/16.5
CZ 50 x 32 -250	50	32	250	12.5	80	100	800	180	225	490	700	675	50	400	370	Ø16		15/20	11/15	2900	19.3/26
CZ 65 x 40 -125	65	40	125	25	20	80	665	112	140	338	604	554	46	338	308	Ø16		5/7.5	3.7/5.5	2900	7/10
CZ 65 x 40 -160	65	40	160	25	32	80	665	132	160	380	604	554	46	338	308	Ø16		7.5/10	5.5/7.5	2900	10/13.7
CZ 65 x 40 -200	65	40	200	25	50	100	800	160	180	430	700	675	50	350	320	Ø16		12.5/15	9.3/11	2900	16.5/19.3
CZ 65 x 40 -250	65	40	250	25	80	100	850	180	225	500	750	700	50	450	410	Ø16		20/30	15/22.5	2900	26/37.5
CZ 80 x 50 -125	80	50	125	50	20	100	700	132	160	380	650	600	50	338	308	Ø16		7.5/10	5.5/7.5	2900	10/13.7
CZ 80 x 50 -160	80	50	160	50	32	100	800	160	180	430	650	600	50	338	308	Ø16		12.5/15	9.3/11	2900	16.5/19.3
CZ 80 x 50 -200	80	50	200	50	50	100	900	160	200	470	750	700	50	450	410	Ø16		20/30	15/22.5	2900	26/37.5

4 POLE (1450 RPM)

Pump Model	Size Description			Nominal duty point		Dimension in millimetres															
	Ø inlet mm	Ø outlet mm	impeller (nominal) mm	Q m³/h	H m	Pump				Support								Motor			
						a	f	h1	h2	h3	m1	m2	m3	n1	n2	S1		hp	kw	rpm	Rated amps
CZ 25 x 25 -125	25	25	125	2	5	82	400	112	142	340	440	400	62	300	270	Ø16		0.25	0.18	1450	0.56
CZ 32 x 25 -125	32	25	125	3	5	82	400	112	142	340	440	400	62	300	270	Ø16		0.25	0.18	1450	0.56
CZ 32 x 25 -150	32	25	150	3	10	82	450	112	142	340	440	400	62	300	270	Ø16		0.5	0.37	1450	1
CZ 50 x 32 -125	50	32	125	6.3	5	80	600	112	140	338	580	530	46	338	308	Ø16		0.5	0.37	1450	1
CZ 50 x 32 -160	50	32	160	6.3	8	80	600	132	160	380	580	530	46	338	308	Ø16		1	0.75	1450	1.7
CZ 50 x 32 -200	50	32	200	6.3	12.5	100	600	160	180	430	650	600	50	350	320	Ø16		1.5	1.1	1450	2.4
CZ 50 x 32 -250	50	32	250	6.3	20	100	650	180	225	490	650	600	50	400	370	Ø16		3	2.2	1450	4.3
CZ 65 x 40 -125	65	40	125	12.5	5	80	600	112	140	338	580	530	46	338	308	Ø16		1	0.75	1450	1.7
CZ 65 x 40 -160	65	40	160	12.5	8	80	600	132	160	380	580	530	46	338	30	Ø16		1.5	1.1	1450	2.4
CZ 65 x 40 -200	65	40	200	12.5	12.5	100	600	160	180	430	650	600	50	350	320	Ø16		2	1.5	1450	3
CZ 65 x 40 -250	65	40	250	12.5	20	100	650	180	225	500	650	600	50	450	410	Ø16		5	3.7	1450	7.8
CZ 80 x 50 -125	80	50	125	25	5	100	650	132	160	380	580	530	50	338	308	Ø16		1.5	1.1	1450	2.4
CZ 80 x 50 -160	80	50	160	25	8	100	700	160	180	430	580	530	50	338	308	Ø16		2	1.5	1450	3
CZ 80 x 50 -200	80	50	200	25	12.5	100	750	160	200	470	650	600	50	450	410	Ø16		5	3.7	1450	7.8

NOTE : 1) All above Motor KW (HP) selection is as per water.
2) Motor KW (HP) will be change as per liquid specific gravity.

CZB Frame Mounted Pump Series - Metalic Magnetic Drive Sealless Chemical Process Pump



Description

- Single Stage, Horizontal Centrifugal Pump.
- Hydraulic Performance and Dimensions according to DIN EN ISO 2858
- Technical design based on DIN EN ISO 15783
- Permanent Magnetic Drive for wide range of temperature.
- Maintenance Free
- Separation of Liquid Chamber to Atmosphere by Means of Isolation Shell
- Slipless Power Transfer
- Materials : Steel, Stainless Steel, Nickel Based Materials
- Close Coupled Block Design
- Hydraulically balanced impeller for minimum bearing loads
- Product-Lubricated Journal Bearings; made of Sintered Silicon Carbide (SSiC) or Customized Materials

Technical Data


Operation Range
Flow Rate : max. 300m³/h
Delivery Head : max. 100 metre
Pressure Rating : Class 150
Temperatures : -35°C to +250°C
Kinematic viscosities : 0.5 to 500 mm²/s

Casing & Impeller Materials

Stainless steel SS 316, SS 316L, SS 304, SS 304L
Other materials duplex alloys , nickel-base alloys
(e.g. Hastelloy®),



Working Principle : Radial flow pump
Stages : Single stage
Priming Method : Flooded suction
Sealing System : Magnetic coupling
Standards : DIN EN ISO 2858
Standards : DIN EN ISO 15783
ATEX : 2014/34/EU
Ex II 2 GD c T2

CZB Frame Mounted Pump Series - Metalic Magnetic Drive Sealless Chemical Process Pump



Pump Model	Size Description			Nominal duty point				Dimension in millimetres																
	Ø inlet mm	Ø outlet mm	impeller (nominal) mm	n 1450 min		n 2900 min		Pump				Support						w	Clearance holes for bolts		Shaft end			
				Q	H	Q	H	a	f	h1	h2	b	m1	m2	n1	n2	n3		S1	S2	d	l		
				m³/h	m	m³/h	m																	
CZB 25 x 25 -125	25	25	125	2	5	4	20	80	312	112	142	50	100	80	190	140	50	270	M12	M10	20	35	15	
CZB 32 x 25 -125	32	25	125	3		5																		
CZB 32 x 25 -150	32	25	150		10		30																	
CZB 50 x 32 -125	50	32	125	6.3	5	12.5	20	80	385	112	140	50	100	70	190	140	110	285	M12	M12	24	50	100	
CZB 50 x 32 -160	50	32	160		8		32			132	160				240	190								
CZB 50 x 32 -200	50	32	200		12.5		50			160	180													
CZB 50 x 32 -250	50	32	250		20		80	100	500	180	225	65	125	95	320	250		370			32	80		
CZB 65 x 40 -125	65	40	125	12.5	5	25	20	80	385	112	140	50	100	70	210	160	110	285	M12	M12	24	50	100	
CZB 65 x 40 -160	65	40	160		8		32			132	160				240	190								
CZB 65 x 40 -200	65	40	200		12.5		50			160	180				265	212								
CZB 65 x 40 -250	65	40	250		20		80	100	500	180	225	65	125	95	320	250		370			32	80		
CZB 80 x 50 -125	80	50	125	25	5	50	20	100	385	132	160	50	100	70	240	190	110	285	M12	M12	24	50	100	
CZB 80 x 50 -160	80	50	160		8		32			160	180				265	212								
CZB 80 x 50 -200	80	50	200		12.5		50			200														
CZB 80 x 50 -250	80	50	250		20		80	125	500	180	225	65	125	95	320	250		370			32	80		
CZB 100 x 65 -125	100	65	125	50	5	100	20	100	385	160	180	65	125	95	280	212	110	285	M12	M12	24	50	100	
CZB 100 x 65 -160	100	65	160		8		32			200					320	250								
CZB 100 x 65 -200	100	65	200		12.5		50			225														
CZB 100 x 65 -250	100	65	250		20		80	125		200	250	80	160	120	360	280		370			32	80	140	

Performance Curves



Industries

- Chemical Processing : basic and fine chemicals
- Agrochemicals, speciality chemicals
- Pharmaceuticals
- Biotechnology processing
- Food and beverage
- Pulp and Paper
- Refinery & Petrochemicals
- Metal processing
- Tanks storage

Processes

- Aseptic Processes
- Chlor-alkali electrolysis
- MDI Processes
- Refrigeration and heating cycles
- Tank unloading
- TDI Processes

Fluids

- Hydrogen peroxide
- Molten Sulphur
- Nitric Acid
- Oleum
- Phosgene
- Phosphoric acid
- Potassium hydroxide solution
- Sodium hydroxide solution
- Sulphuric acid
- Toluene
- Solvents
- Alkalis
- Toxic liquids
- Corrosive liquids

Basic Components



Cartridge Bearing



Impeller



Drive Magnet



Casing



Casing Cover



Can



Driven Magnet



Shaft



CM PUMPS AND SYSTEMS PVT. LTD.

Manufacturer of Magnetic Drive Sealless Pumps & Agitators

Regd. Office:

Unit No. 10, 1st Floor, Shamroz Industrial Estate, Ram Mandir Road,
Goregaon (W), Mumbai - 400 104, Maharashtra, INDIA

Mob: +91-8879002681 **Tel.:** +91-22-49672681/82

✉ info@cmpumps.com 🌐 www.cmpumps.com

Factory Unit I :

Survey No. 257/1, Plot No. 36 & 37, Khali Char Rasta,
Near Meena Hotel, Village Khali, Taluka Siddhpur,
Dist. Patan - 384151. Gujrat (INDIA)

Factory Unit II :

Plot No. 191/192, Siddhpur GIDC, Taluka Siddhpur,
Dist. Patan - 384151. Gujrat (INDIA)